

City of Cambridge

PURCHASING DEPARTMENT

SHUO WANG

Assistant Purchasing Agent for Goods & Services

NATALIE SULLIVAN

Assistant Purchasing Agent for Design & Construction

TO: All Bidders

FROM: City of Cambridge

DATE: May 23, 2024

RE: File No. 11571 – Webster Ave Demolition - Addendum No. 2

This addendum is comprised of the following:

- 1. Changes to Specifications
- 2. Changes to Drawings
- 3. Questions and Answers

CHANGES TO SPECIFICATIONS

Section 012300 – Alternates

Delete this section in its entirety:

Section 024100 – Demolition Replace this section with the attached section 024100."

CHANGES TO DRAWINGS:

AD-100 – 315 Webster Avenue Demolition Plans Replace this drawing with the attached drawing AD-100

S-100 – 319 Webster Avenue Temporary Roof Truss Shoring Replace this drawing with the attached drawing S-100

Existing Conditions Survey

A drawing of the existing conditions survey is being provided.



The following questions were asked and answered:

Question 1:

Although Building 333 Webster is included in the Asbestos Report, please confirm that it is NOT INCLUDED in this contract scope

Response:

The asbestos report states "The site consists of two (2) addresses (319 Webster Street and 33 Webster Street). Two (2) buildings exist on each address. The two buildings located at 319 Webster Street at scheduled to be demolished." (It was meant to say 333 Webster not 33 Webster) However, neither 333 nor 333A are included in the scope.

Question 2:

Please confirm that we can utilize the hydrant near 333 Webster on the same side of the street as 315 Webster for dust control.

Response:

Confirmed. The hydrant located near 94 Webster Ave can be used, but the contractor must apply for a Hydrant Meter Permit from the City of Somerville prior to use

Question 3:

From that Asbestos Report, there was none detected at 327 Webster, although there is a listing for some minor hazardous materials abatement? What was anticipated?. Response:

The asbestos report initially anticipated hidden pipe and hard joint insulation and hidden transite pipe that might be found.

The asbestos report refers to "319 South Building" "319 North Building" "333 South Building" and "333 North Building".

319 South Building in the report is the building at 315 Webster

319 North Building in the report is the building at 327 Webster

333 South Building in the report is the building at 333 Webster

333 North Building in the report is the building at 333A Webster



Question 4:

Please confirm that we are not removing any former underground foundations

Response:

The top 2-feet of the concrete basement walls of the building at 315 Webster and top 2-feet of the foundation supporting the immediately adjacent canopy columns is being removed.

The complete foundation of the building at 327 Webster and the complete foundation supporting the immediately adjacent canopy columns is being removed.

No other foundations are being removed.

Question 5:

There are only two photos of the basement (15 and 16 on AD-101) which are fairly dark. Please provide more photos of the basement area (at least every wall plus some of the first floor underdeck condition) as well as any possible debris inside. We were not able to access the basement at the site walk..

Response:

Photos of the basement are on the pages that follow.

Question 6:

For the Add Alternate, if the former owner thought that they needed shoring for the floor or roof as shown on S-100, there must have been a structural concern for stability. If we were to remove that shoring first, it may put our crew in danger of an unstable or compromised structure. We believe that the ADD Alternate should be removed from the scope. We suggest that Cambridge check with your Architect for confirmation. That shoring would most likely be damaged during demolition and rendered useless.

Response:

The Add Alternate has been removed from the bid documents.



ATTACHMENTS


Photo Attachments of basement level. The specification sections noted above The drawings noted above.

All other details remain the same.

Elizabeth Unger Purchasing Agent


Addendum No. 2











SECTION 024100 - DEMOLITION

PART 1 - GENERAL

1.01 GENERAL PROVISIONS

A. Attention is directed to the Contract and General Conditions and all Sections within Division 01 - General Requirements, which are hereby made a part of this Section of the Specifications.

1.02 DESCRIPTION OF WORK

A. Work Included:

- 1. Demolition and removal of buildings and structures and as required for new work. Refer to the Drawings for additional requirements.
- 2. Demolition and removal of selected site elements and as required for new work. Refer to the Drawings for additional requirements.
- 3. Both abandoning in place and removing below-grade construction
- 4. Disconnecting, capping or sealing, and abandoning in place site utilities
- 5. Removal and legal disposal of demolished materials off site. Except those items specifically designated to be relocated, reused, or turned over to the facility, all existing removed materials, items, trash and debris shall become property of the Contractor and shall be completely removed from the site and legally disposed of at her/his expense. Salvage value belongs to the Contractor. On-site sale of materials is not permitted.
- 6. Protection of trees, utilities and other adjacent structures from damage resulting from work under this section.
- 7. Scheduling and sequencing operations without interrupt utilities serving occupied areas. If interruption is required, obtain written permission from the utility company and the City of Cambridge Project Manager. Provide temporary services as necessary to serve occupied and usable facilities when permanent utilities must be interrupted, or schedule interruption when the least amount of inconvenience will result.

B. Add Alternate Work Included:

1. None.

C. Related Sections

- Section 013543 Environmental Procedures: Removing or remediating all hazardous waste materials.
- 2. Section 017419 Construction Waste Management
- 3. Section 028200 Asbestos Remediation: ACM removal

1.03 DEFINITIONS

- A. Remove: Detach items from existing construction and legally dispose of them off-site, unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Detach or relocate items from existing construction work area and deliver or relocate them as directed to a designated location. Protect from weather until accepted by City of Cambridge.

- C. Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated. Protect from weather until reinstallation.
- D. Existing to Remain: Existing items of construction that are not to be removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.04 MATERIALS OWNERSHIP

A. Historic items, relics, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques, antiques, and other items of interest or value to the City of Cambridge that may be encountered during selective demolition remain property of the City of Cambridge as applicable. Carefully remove each item or object in a manner to prevent damage and deliver promptly to a location acceptable to the City of Cambridge.

1.05 SUBMITTALS

- A. Schedule of Selective Demolition Activities: Indicate the following:
 - 1. Detailed sequence of selective demolition and removal work, with early and late starting and finishing dates for each activity. Ensure User Agency's on-site operations are uninterrupted if applicable.
 - 2. Interruption of utility services. Indicate how long utility services will be interrupted.
 - 3. Coordination for shutoff, capping, and continuation of utility services.
 - 4. Locations of proposed dust- and noise-control temporary fencing and means of egress, including for other occupants affected by demolition operations.
 - 5. Coordination of City of Cambridge 's continuing occupancy of portions of the existing site.
 - 6. Means of protection for items to remain and items in path of waste removal from building.
 - 7. Plan for fire prevention during demolition.
- B. Pre-demolition Photographs and Videos: Show existing conditions of adjoining construction and site improvements, including the interior and finish surfaces, that might be misconstrued as damage caused by selective demolition operations. Comply with Division 01. Submit before Work begins.

1.06 QUALITY ASSURANCE

- A. Examination of Existing Conditions: The Contractor shall examine the Contract Drawings for demolition and removal requirements and provisions for new work during the scheduled pre-bid walk-through. (See Instructions to Bidders) Verify all existing conditions and dimensions before commencing work. At such time, the Contractor shall examine the existing conditions as he/she finds them and shall inform herself/himself of the character, extent and type of demolition and removal/relocation work to be performed. Submit any questions regarding the extent and character of the demolition and removal work in the manner and within the time period established for receipt of such questions during the bidding period.
- B. Demolition Firm Qualifications: An experienced firm that has specialized in demolition work similar in material and extent to that indicated for this Project.
- C. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.

- D. Standards: Comply with ANSI A10.6 and NFPA 241.
- E. Predemolition Conference: Conduct conference at Project site to comply with requirements in Section 013100 Project Management and Coordination. Review methods and procedures related to selective demolition including, but not limited to, the following:
 - 1. Inspect and discuss condition of construction to be selectively demolished.
 - 2. Review structural load limitations of existing structure.
 - 3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
 - 4. Review requirements of work performed by other trades.
 - 5. Review areas where existing structures are to remain and requires protection.

1.07 PROJECT CONDITIONS

- A. Buildings to be demolished will be vacated and their use discontinued before start of Work..
- B. The building immediately adjacent to demolition area will be occupied. Conduct building demolition so their operations will not be disrupted.
- C. Maintain access to existing walkways, exits, and other adjacent occupied or used facilities.
- D. Owner assumes no responsibility for buildings and structures to be demolished.

1.08 WARRANTY

E. Existing Warranties: Remove, replace, patch, and repair materials and surfaces damaged during demolition, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Verify that utilities have been disconnected and capped.
- B. Inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged.
- C. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to the Architect.

3.02 UTILITY SERVICES

A. The Owner will locate, identify, disconnect, and seal or cap off utility services serving buildings to be demolished.

3.03 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit after bypassing. Where entire wall is to be removed, existing services/systems may be removed with removal of the wall.
- B. Prior to commencing cutting work in existing surfaces, take all precautionary measures to assure that mechanical and electrical services to the particular area have been made inactive. Only licensed tradesmen of that particular trade shall disconnect and cap existing mechanical and electrical items that are to be removed and / or abandoned
- C. If, during the process of cutting work, existing utility lines are encountered which are not indicated on the Drawings, regardless of their condition, immediately report such items to the Architect. Do not proceed with work in such areas until instructions are issued by the Architect. Continue work in other areas

3.04 PREPARATION

- A. Site Access and Temporary Controls: Conduct demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - Comply with requirements for access and protection specified in Section 015000 -Temporary Facilities And Controls.
 - 2. Maintain adequate passage to and from all exits at all times. Before any work is done which significantly alters access or egress patterns, consult with the Architect and obtain approval of code required egress. Under no condition block or interfere with the free flow of people at legally required exits, or in any way alter the required condition of such exits.
- B. Temporary Shoring: Provide and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.
 - 1. Remove temporary shoring, bracing and structural supports when no longer required.
 - 2. Post warning signs and place barricades as applicable during placement and removal of temporary shoring.
- C. Conduct demolition operations to prevent injury to people and damage to adjacent buildings and facilities to remain. Ensure safe passage of people around demolition area(s).
 - 1. Erect temporary protection, such as walks, fences, railings, canopies, and covered passageways, where required by authorities having jurisdiction. Provide temporary barricades as required to limit access to demolition areas.
 - 2. Protect existing site improvements, appurtenances, and landscaping to remain.
- D. Drain, purge, or otherwise remove, collect, and dispose of chemicals, gases, explosives, acids, flammables, or other dangerous materials before proceeding with demolition operations.

3.05 DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
 - 1. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain fire watch and portable fire-suppression devices during flame-cutting operations.
 - 2. Maintain adequate ventilation when using cutting torches.
 - 3. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
 - 4. Locate demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
 - 5. Dispose of demolished items and materials promptly.
- B. Removed and Salvaged Items:
 - 1. Clean salvaged items.
 - 2. Pack or crate items after cleaning. Identify contents of containers.
 - 3. Transport items to storage area designated by the City of Cambridge.
 - 4. Protect items from damage during transport and storage.

3.06 PROTECTION OF PUBLIC AND PROPERTY

- A. Provide all measures required by federal, state and municipal laws, regulations, and ordinances for the protection of surrounding property, the public, workmen, and City's employees during all demolition and removal operations. Measures are to be taken, but not limited to installation of sidewalks, sheds, barricades, fences, warning lights and signs, trash chutes and temporary lighting.
- B. Protect all walks, roads, streets, curbs, pavements, trees and plantings, on and off premises, and bear all costs for correcting such damage as directed by the Designer, and to the satisfaction of the City of Cambridge Project Manager.
- C. Demolition shall be performed in such a manner that will insure the safety of adjacent property. Protect adjacent property from damage and protect persons occupying adjacent property from injuries which might occur from falling debris or other cause and so as not to cause interference with the use of other portions of the building, of adjacent buildings or the free access and safe passage to and from the same.
- D. Every precaution shall be taken to protect against movement or settlement of adjacent buildings, sidewalks, roads, streets, curbs and pavements. Provide and place at the Contractor's own expense, all necessary bracing and shoring in connection with demolition and removal work.
- E. Remove portions of structures with care by using tools and methods that will not transfer heavy shocks to existing and adjacent building structures, both internal and external of the particular work area.
- F. Provide and maintain in proper condition, suitable fire resistive dust barriers around areas where interior demolition and removal work is in progress. Dust barriers shall prevent the dust migration to adjacent areas. Remove dust barriers upon completion of major demolition and removal in the particular work area.

3.07 DISCOVERY OF HAZARDOUS MATERIALS

- A. If hazardous materials, such as chemicals, asbestos-containing materials, or other hazardous materials are discovered during the course of the work, cease work in affected area only and immediately notify the Architect and the Owner's Project Manager of such discovery. Do not proceed with work in such areas until instructions are issued by the Architect. Continue work in other areas.
- B. If unmarked containers are discovered during the course of the work, cease work in the affected area only and immediately notify the Architect and the Owner of such discovery. Do not proceed with work in such areas until instructions are issued by the Architect. Take immediate precautions to prohibit endangering the containers integrity. Continue work in other areas.

3.08 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Comply with the following.
 - 1. Do not allow demolished materials to accumulate on-site.
 - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
 - 3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
- B. Burning: Do not burn demolished materials.

3.09 DUST CONTROL AND CLEANING

- A. Spray water onto demolition sufficient to prevent dust.
- B. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Premises shall be left in a clean condition and ready to accept alteration work and new construction.

END OF SECTION

BASEMENT FLOOR PLAN

1/4" = 1'-0" + / -



24 Roland Street Charlestown, MA 02129 T: 617.776.6545 F: 617.776.6678 www.hktarchitects.com

Number Revision 1 ADDENDUM 02 5/23/2024

Registrations


Consultants

 Ω

22321 Job number

Construction Documents

Plan View at First Level Shoring Frames



² Plan View at Basement Shoring Frames Scale: N.T.S.

THIS DRAWING WAS PREPARED BY OTHERS AND IS BEING PROVIDED TO ESTABLISH THE EXTENT OF THE EXISTING SHORING AND IS FOR REFERENCE ONLY. FIELD VERIFY ALL CONDITIONS.

ALL EXISTING SHORING IS TO BE REMOVED AS PART OF THE **DEMOLITION OF THIS BUILDING LOCATED AT 315 WEBSTER AVE.**

ADD ALTERNATE: NONE INCLUDED.

TRINGER BEAMS ON HEADER BEAMS ON SHORING FRAMES; BUILDING WIDTH=30 FT Frames: 10'-6" ± Tall **Shoring Frames** 1.9" Ø steel post and ledgers / shoring frames frames w/ screw jacks, locking pins, wood sills, and diagonal bracing all sides, fit tight to bearing for support of existing max ledgers all sides < 12" jack extension Frames: 6'-6" ± Tall Frame Elevation

System / Assembly Notes

BY AN INDUSTRY MANUFACTURE OF SCAFFOLD AND COMPONENTS ARTS DESCRIBED HEREIN ARE TO BE REFERENCED TO THE INDUSTRY ANDARD MANUFACTURES LOAD RATING CATALOG COMPONENT TESTING CONNECTION AND MEMBER CAPACITIES OR SUPPLIED COMPUTATIONS. PROWDE MECHANICAL CONNECTORS & CLAMPS FOR ALL COMPONENTS

2.) USER A ERECTOR / COMPETENT PERSON SHALL COMPLY WITH ALL OSHA, LOCAL AND NATIONAL STANDARDS FOR SCAFFOLDING

3.) THE PLANS DEVELOPED FOR THIS APPLICATION HAVE BEEN BASED ON THIRD PARTY SUPPLIED INFORMATION AND MAY VARY DUE TO FIELD CONDITIONS AND SITE CHANGES. THE END USER MUST PERFORM INITIAL AND ONGOING INSPECTIONS ON

INTERVALS AS REQUIRED FOR CONFORMANCE TO STANDARDS BY LOCAL, STATE AND NATIONAL CODE ENFORCEMENT AUXHORITIES 4.) ERECTOR TO CHECK AND VERIFY ALL DIMENSIONS AND DETAILS PRIOR

TO INSTALLING

5.) MATERIAL NOTES: ALL STANDARDS ARE STEEL PIPE TYPE 1 HAVING MINIMUM O.D. = 1.9" AND WALL THICKNESS = 0.120" WALL, y=50 KSI material

6.) USE LOAD BEARING ROSETTE FITTINGS FOR ALL SECTIONS, TUBE & Y PERMITTED AT DIAGONAL ASSEMBLY, FITTING / CLAMP ALTERNATIVE ALL BRACING TO EXTEND TO A MINIMUM OF TWO STANDARDS

7.) ALL JOINTS MUST BE FIXED WITH LOCKING PINS, BEAMS W/ CLAMPS, TYPICAL.

8.) ALL STANDARD 70 BE BRACED IN TWO DIRECTIONS AT MAXIMUM OF 40", UNLESS OTHERWISE NOTED.

9.) ALL FRAMES TO HAVE DIAGONAL BRACING ON EACH SIDE, LONGITUDINAL AND TRANSVERSE, HAVING INDIVIDUAL FRAMES LINKED TOGETHER OR BRACED ON ALL SIDE FOR TOWER ASSEMBLIES

10) ALL PLATFORM EDGES T HAVE 4" MIN. TOE BOARDS PROTECTION AT

ALL STAIR AND PLATFORMS TO BE KEPT CLEAR OF DERBIES, ALL

NOW, ICE ETC. TO BE REMOVED BEFORE USE 12) OVER HEAD PROTECTION TO HAVE SCAFFOLD PLANKS AND $\frac{3}{4}$ " PLYWOOD SIDE WALL RAILS AND ENCLOSURE SYSTEM BY CLIENT SELECTION

General Notes

Project Location:

Cambridge, Massachusetts Massachussetts State Building Code Roof Dead Load; DL= 25 psf with ASCE 7 - 10.

Roof Snow Pf= 30 psf ound Snow= N/A Interior Seismic S1 = 0.216 Ss = 0.069Soil Bearing = 2,500 psf u.o.n.

 ALL SHORING PROVIDED FOR GRAVITY LOADING, **ROOF FRAMIN** TURE IS UNDERSTOOD TO BE MAI SUPERSTRUC^{*} OVERALL BUILDING STABILITY


ALL SCAFFOLD COMPONENTS AND SET JPS ARE AS PER INDUSTRY AND OSHA STANDARD PARTS NOT EXPLICITLY DI ACTURES CATALOG COMPONENT TO INDUSTRY STANDARD M TESTING AND CONNECTION AND MEMBER CAPACITIES

USER / ERECTOR / COMPETENT PERSON SHALL COMPLY WITH ALL OSHA, LOCAL AND NATIONAL STANDARDS FOR SCAFFOLDING


THIS LAYOUT WAS DEVELOPED FROM LIMITED INFORMATION AND RFORM INSPECTIONS ON INTERVALS AS REQUIRED BY THE MANUFACTURE, ANSI, LOCAL STATE AND NATIONAL

R TO CHECK AND VERIFY ALL DIMENSIONS AND DETAILS

Typical Rosette Standard Assembly



Typical Ring Standards Parts



* Horizontal 2-2, Ledger Y-Y direction not more than 20"

5/23/24 ADDENDUM 02

g ambri 0 \Im

Shoring

October 2023

Sheet No.

S -100

