
# ROUTE 2 ALEWIFE ACCESS ROAD BUS-ONLY LANE CONCEPT

January 2020




#### Route 2 Corridor: Alewife Access Road





### Ridership and 90<sup>th</sup> Pct. Delay: 7am – 9am





# Ridership and 90th Pct. Delay: 4pm - 7pm





#### Peak Hour Person Throughput (7-9 AM and 4-7 PM)

Corridor	Segment	Car	Bus	Truck
Route 2   to Alewife	Route 2   Lake Street Overpass to Lake Street Onramp	92%	6%	2%
Route 2   to Alewife	Route 2   Lake Street Onramp to MA-16	90%	8%	2%
Route 2   to Alewife	Steel Place (continued from access road) to Alewife Busway	65%	35%	0%
Route 2   to Arlington	Alewife Busway to MA-16 via dog leg	65%	35%	0%
Route 2   to Arlington	Route 2   MA-16 to Lake Street Offramp	90%	8%	2%
Route 2   to Arlington	Route 2   Lake Street Offramp to Lake Street Onramp	93%	6%	2%

- HPMS data based on average private vehicle occupancy and automatic passenger count data from the MBTA
- Data represents percent people (not vehicles)



#### **Issues and Opportunity**

- Buses slow after right turn from Acorn Park Drive onto the inbound Alewife Access Rd
- Vehicles queue waiting to turn left at the end of the off ramp due to pedestrian crossing
- Inbound Access Road is wide enough to split into two lanes

#### **Benefits of Transit Priority**

- At 50<sup>th</sup> percentile travel times, people riding the bus will save a **cumulative 12.2 hours** each day
- At 90<sup>th</sup> percentile travel times, people riding the bus will save a cumulative 22.0 hour each day



#### **Proposed Concept: Create a Right Lane Bus Lane**






#### Right Lane Bus Lane Auto-turn at Acorn Park Drive






# Right Lane Bus Lane Auto-turn around Curve





#### **Turning Volume**

- From the CTPS 2009 memo
- Most drivers coming off the Alewife ramp go straight—doubled in the PM





#### **Project Timing**

MassDOT needs to complete bridge repairs prior to implementation of a bus lane.

- Developing a detailed scope of work and cost estimate for this work
- Includes attached utilities and work to be completed above water
- Design work is to tentatively planned to be completed in late Spring
- State funding for completing bridge work not yet identified
- Bridge remains safe for ongoing operation





#### **Next Steps**

- Continue working with MassDOT to identify construction funding
- Identify design solution for end of bus lane ramp working with the City of Cambridge, DCR, MassDOT, and MBTA
- Consider interim bus lane options if construction funding is delayed

# Questions?

