





Curtain wall glass: InterPane Stopray Ultra 70 CSV, double-glazed VLT: 67%, Reflectivity out: 10% Winter U value: 0.23,


Deep red reduction-fired

Materials

terracotta


Curtain wall fin:

Summer U value: 0.21, SHGC: 0.29, 12mm air




Curtain wall mullion:

Metal with dark medium-grey Duranar XL Deep Space



Metal with medium-grey paint Benjamin Moore CSP-20 Wall Street
















Pilaster panel: Pure+Freeform red-grey printed aluminum panel

Pilaster panel (contrast): Pure+Freeform copper-grey printed aluminum panel

Curtain wall, mullion, spandrel and stormproof louver: Metal with medium-dark grey paint Duranar XL Deep Space














Storefront glass: IBG low-iron glass, iplus 1.1 10-12-6 CLV Air ER VLT: 84% Reflectivity out: 12% SHGC: 0.60 Winter U value: 0.29 Summer U value: 0.28

Storefront mullion, liner metal and reveal: Metal with medium-dark grey paint Duranar XL Deep Space

Liner underside: PVDF Prodema pale

Storefront base: Jet Mist granite



















Public elevator vestibule, eastside alley panels: Dura Artisan Cor-Ten Light painted aluminum

Bike room vestibule, garage vestibule:

Deep red to deep gold gradient of ceramic tile Bisazza GM 20.97, Bisazza SM 74

East-side windows:

IBG low-iron glass, iplus 1.1 10-12-6 CLV Air ER VLT: 84% Reflectivity out: 12% SHGC: 0.60 Winter U value: 0.29 Summer U value: 0.28

Bendheim Houdini channel glass:

VLT: 72%

Reflectivity out: 8%*

SHGC: 0.66 U value: 0.49

East-side window mullions, louvers: Benjamin Moore 2125-20 Deep Space

^{*} Manufacturer has stated that this reflectivity is equivalent to national standards.






East-side windows







Vehicle door portals: Dura Artisan Cor-Ten Light painted aluminum

(note: painted materials vary; sample shown represents intent but final selections may have slight variations)

Overhead door opaque panels:

Metal with medium-dark grey paint

Duranar XL Deep Space

Overhead door translucent panels:

Rytec Spiral FV high-speed overhead door, translucent lexan





Interior bicycle rack: Landscape Forms FGP bike rack Finish: anodized



Polished concrete floor and ramp with a 0.43 coefficient for friction (required slip resistance)






InterPane Stopray Ultra 70 CSV VLT: 67%, Reflectivity out: 10% Winter U value: 0.23, Summer U value: 0.21, SHGC: 0.29, 12mm air

Location

Northeast and northwest curtain wall façades;

Southeast and southwest façades





InterPane Stopray Ultra 70 CSV with White Ceramic Frit

Location

Northeast and northwest curtain wall façades






Shildan deep-red terra cotta

Location

Northeast and northwest curtain wall façades





Metal with medium-dark grey paint Duranar XL Deep Space

Location

Northeast and northwest curtain wall mullions

Southeast and southwest mullions, spandrels and stormproof louvers

Northwest façade overhead door opaque panels

East-side window mullions

Northeast façade, mechanical penthouse area expanded metal mesh

Portal liner outer surface

Northeast and southwest corners, reveal between curtain wall and pilaster wall

Glazed entrance mullions

Opaque loading dock doors

CURTAIN MULLION, STORMPROOF LOUVER, OVERHEAD DOOR PANELS, PENTHOUSE MESH









Metal with medium grey paint Benjamin Moore CSP-20 Wall Street

Location

Northeast and northwest curtain wall façades, shadowbox









Pure+Freeform printed aluminum

Location

Southeast and southwest façades







Pure+Freeform printed aluminum

Location

Southeast and southwest façades, shifted volumes





IBG low-iron glass, iplus 1.1 10-12-6 CLV Air ER

VLT: 84%

Reflectivity out: 12%

SHGC: 0.60

Winter U value: 0.29 Summer U value: 0.28

Location

First floor, lobby and northwest

First floor, bike room



PVDF coated wood - dark brown

Location

First floor, lobby, northwest and northeast, portal liner inner surface and horizontal louvered







Dura Artisan Cor-Ten Light painted aluminum

(note: painted materials vary; sample shown represents intent but final selections may have slight variations)

Location

Loading dock and parking portals

East and northeast façades

Public elevator vestibule

Stormproof louvers





Rytec Spiral FV high speed overhead door

Location

Loading Dock







CERAMIC TILE MOSAIC WALL




Material

Deep red to deep gold gradient of ceramic tile Bisazza GM 20.97, Bisazza SM

Location

First floor, bike room vestibule and garage elevator vestibule



Bendheim Houdini channel glass

VLT: 72%

Reflectivity out: 8%*

SHGC: 0.66 U value: 0.29

Location

Bike room east-side windows

* Manufacturer has stated that this reflectivity is equivalent to national standards.





Jet Mist honed granite

Location

18" vertical base of building

















